



अखिल भारतीय आयुर्विज्ञान संस्थान (एम्स) कल्याणी
All India Institute of Medical Sciences (AIIMS) Kalyani
(स्वास्थ्य एवं परिवार कल्याण मंत्रालय, भारत सरकार के तत्वावधान में एक सांविधिकनिकाय)
(A Statutory Body under the Aegis of Ministry of Health and Family Welfare, GOI)
राष्ट्रीय राजमार्ग – 34, बसन्तपुर, सागुना, कल्याणी, ज़िला – नदिया, पश्चिम बंगाल - 741245
NH-34 Connector, Basantapur, Saguna, Kalyani, District Nadia, West Bengal 741245

Ref No : 428/M-11011/1/24-25(IM)/Anatomy/FA/898

Dated :26/11/2024

E-Tender No: 376/M-11011/1/24-25(IM)/Anatomy/FA/898/ET-22

Date: 07.11.2024

1st Corrigendum of E-Tender for DESIGN, SUPPLY, INSTALLTION AND COMMISSIONING OF WALK IN COLD ROOM FOR THE DEPARTMENT OF ANATOMY, AIIMS KALYANI

Sl No	Point	Written as	To be Read as
1.	PAGE 5 of the Tender Document	Amount of Earnest Money Deposit (EMD)(in shape of DD/BG): 50,000	Amount of Earnest Money Deposit (EMD)(in shape of DD/BG): 75,000
2.	POINT NO. 24 at PAGE 13 of the Tender Document	Turnover: The average annual turnover for last 03 (three) financial year ending on 31/03/2024 must be AT LEAST 100 lakhs.	Turnover: The average annual turnover for last 03 (three) financial year ending on 31/03/2024 must be AT LEAST 7.5 lakhs.
3.	POINT NO. 3 of Technical Specifications at PAGE 14 of the Tender Document	REQUIRED ROOM TEMPERATURE: (-)20 deg C (Tolerance : minus 3 degrees Celsius tolerance on plus side)	REQUIRED ROOM TEMPERATURE: Minus 23 to Minus 20 Degree Centigrade throughout the year under local conditions Note: "A suitable refrigerant from the list of CFC and HCFC free refrigerants given in appendix N of general specification 2017 for HVAC work published by CPWD" will be selected
4.	POINT NO. 9 of Technical Specifications at PAGE 14 of the	Lamination of Panels (Wall & Ceiling): PP/PP Inside and outside 125 MM PUF panels (or thicker in order to meet desired result)	Lamination of Panels (Wall & Ceiling): 125 mm thick PUF layer inside panels made of either Poly Propylene coated GI or a

	Tender Document		combination of PP coated GI on one face and SS304 on other face
5.	PAGE 22 of the Tender Document	<p>FACILITIES TO BE PROVIDED AT SITE:</p> <p>Items of work listed below are not included in our scope of work and the quoted price and are to be provided by the customer at site;</p> <p>Provision of any major or minor civil work, masonry work including fabrication and grouting of frame/platform for Condensing/Evaporator units.</p> <p>Provision for supports for ceiling/wall panels and Refrigeration units like truss work, suspension rods etc. if required. Proper ventilation for the Refrigeration units to be provided at site.</p> <p>Provision of site drawing / layout & internal layout.</p> <p>Provision of 415/230 V, 3/1 phase, 50 Hz stabilised power supply ending in suitable Plug & socket type MCB within one meter radius of the condensing unit, distribution boards etc with Single phase preventors etc.</p> <p>Provision of drain traps & drain plumbing as per building's original provisions.</p>	Deleted

Consequent to the approval of the competent authority, the above-mentioned tender is hereby extended for 14 days from the date of this notification on the official website of AIIMS Kalyani and CPPP.

(Prof.) Dr. Mahuya Chattopadhyay
Chairperson of Procurement Cell
AIIMS Kalyani